



ADDENDUM NO. 03

To: Bidders & Plan Holders

From: Craig A. Johnson, P.E.
Crist Engineers, Inc.

Date: June 21, 2024

Project: Central Arkansas Water
Intake Gate Replacement
Lake Maumelle and Lake Winona

Bid Date: June 25, 2024

Bid Time: 2:00 PM

Location: Central Arkansas Water – Engineering Department
4th Floor Conference Room
221 East Capitol Avenue, P.O. Box 1789
Little Rock, Arkansas 72203-1789

The BIDDER shall properly acknowledge Addendum No. 02 as required in Article 3 of Document 004100 on the Bid Form as confirmation that the BIDDER has examined the following Addenda and the related changes to the Contract Documents. Lack of proper acknowledgement on the Bid Form may deem a bid non-responsive.

The Contract Documents dated May 24, 2024, are hereby amended as follows:





Bidders & Plan Holders
Addendum No. 03
Intake Gate Replacement
Page 2 of 2

IMPORTANT REMINDERS:

Please reference Section 002113 - Instructions to Bidders, provided in the contract documents for information required for the bid submission.

SPECIFICATIONS:

Division 40 – Process Integration:

1. **Section 40 05 59 Stainless Steel Slide Gates and Weir Gates**
 - a. 2.2 Gate Schedule: Please see updated Gate Schedule.

Slide Gate Schedule

Location	Name	QTY	Inv. El. (FT.)	Size	Type	Mounting	Operator	Mounting Position	Actuator Service
Lake Maumelle	M-1	1	245.75	72"x72" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Maumelle	M-2	1	262.50	72"x72" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Maumelle	M-3	1	282.50	72"x72" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Winona	W-1	1	729.00	48"x60" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Winona	W-2	1	713.00	48"x60" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Winona	W-3	1	699.00	48"x60" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Lake Winona	W-4	1	683.00	48"x60" Opening	Non-Self-Contained	Wall Mounted	Hand Crank	Standard	Open/Close
Head Pressure for all Lake Winona Gates: 67'									
Head Pressure for all Lake Maumelle Gates: 54'									

END ADDENDUM NO. 03